



- NOTES:**
1. THE LOCATION AND EXTENT OF THE REMOVAL AND REPLACEMENT OF VARIOUS ITEMS INCLUDING, BUT NOT LIMITED TO 6"x8"x18" CONCRETE CURB, 6" CONC. DRIVEWAY APRON, 6" CONC. SIDEWALK, 4" CONC. SIDEWALK AND ANY OTHER ITEMS INCLUDED IN THE BID PROPOSAL SHALL BE DELINEATED IN THE FIELD BY THE EAST WINDSOR TOWNSHIP ENGINEER UP TO THE TOTAL QUANTITIES SPECIFIED IN THE BID PROPOSAL, UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
 2. CONSTRUCTION OF NEW HANDICAP RAMPS SHALL INCLUDE THE REMOVAL AND INSTALLATION OF UP TO FOUR (4) ADJOINING 4' CONCRETE SIDEWALK PANELS. PAYMENT SHALL BE INCLUDED IN ITEM: **NEW HANDICAP RAMPS**.
 3. EXISTING ASPHALT DRIVEWAYS SHALL BE SAWCUT A MAXIMUM OF 4' FROM THE SIDEWALK TO ADJUST THE DRIVEWAY GRADE TO MEET THE NEW CONCRETE SIDEWALK OR DEPRESSED CURB, IF AND WHERE DIRECTED. THE DRIVEWAY SHALL BE RESTORED WITH 4" THICK BITUMINOUS CONCRETE SURFACE COURSE MIX I-5. PAYMENT FOR SAWCUTTING, ASPHALT REMOVAL, GRADE ADJUSTMENT AND NEW ASPHALT INSTALLATION SHALL BE MADE UNDER PAY ITEM: **ASPHALT DRIVEWAY APRONS 4"**.
 4. PROPOSED LINE STRIPING SHALL BE INSTALLED IN THE LOCATION AND CONFIGURATION SHOWN ON THE PLANS. PAYMENT SHALL BE INCLUDED FOR ALL THESE ITEMS, REGARDLESS OF TOTAL WIDTH AND COLOR IN PAY ITEM: **LINE STRIPING**. THE TOTAL QUANTITY WILL BE MEASURED IN 4' WIDE INCREMENTS.
 5. NO SEPARATE PAYMENT SHALL BE MADE FOR ASPHALT PAVEMENT RESTORATION ASSOCIATED WITH CONCRETE CURB CONSTRUCTION OR REPLACEMENT. THE COST FOR THIS WORK SHALL BE INCLUDED AS SPECIFIED IN PAY ITEMS: **CONCRETE CURB, REMOVE AND REPLACE OR NEW CONCRETE CURB**. SEE CONCRETE SIDEWALK & DRIVEWAY APRON DETAIL.

CONSTRUCTION PLAN			
ROAD IMPROVEMENTS FOR LYNNFIELD DRIVE			
DRAWN:	MBL	DATE	NO.
APPROVED:	RC		
DATE:	4/12/23		
SCALE:	1" = 30'		
SHEET NO.	3 of 5		
EAST WINDSOR TOWNSHIP			
MERCER COUNTY, N.J.			
16 LANNING BOULEVARD			
EAST WINDSOR, N.J.		REVISIONS	